

# Getting Started with Prefab




Research and Education for the Electrical Construction Industry

Josh Bone Executive Director, ELECTRI International josh.bone@electri.org

## Industrialized Construction



Industrialized Construction - The industrialization of construction is the process through which construction aims to improve productivity through increased mechanization and automation. The process commonly involves modularization, prefabrication, preassembly, and mass production





# Merck has released an initiative for all construction to be 80% fabricated offsite by 2025



Vision: Safely and effectively deliver >\$15B in capital to enable 1B more patients served.



Fortify our Future







2025 Strategic Imperatives

Protect Safety First, Quality Always 0 Incidents, 0 Defects

**Build** our Future - Workforce and Facilities

New Design Thinking and MPS Capabilities Agile Solutions with Digitally Enabled Results

Transform our Business

40% Less, 80% Offsite - Capital Effectiveness



### Comparing work in the Shop to the Field



		Shop	Field
HOURLY LABOR RATE \$ MIN.CHARGE	Labor Rate	\$75/Hr.	\$110/Hr.
	Single Clevis Hanger	3 Minutes	10 Minutes
	Single Tier Trapeze Hanger	6 1/2 Minutes	17 Minutes

### **Advances in Digital Fabrication**

TigerStop and RazorGage





### **Advances in Digital Fabrication**

TigerStop and RazorGage





### Standardization evolves into Productization





# Panel Builder Program





# Conduit Bending








#### What are others doing?



# CONSTRUCTION MANUFACTURING





DOWNLOAD SPEC SHEET

#### UNDERGROUND HORIZONTAL DUCTBANK

**APPLICATIONS** 

https://www.excelleratemfg.com/





## The Competition is Evolving



#### **RISE Modular**

6,359 followers

1h • 🔇

It's always 70 degrees at RISE and we are hiring!

If you are a t-shirt wearing drywaller, plumber, electrician, carpenter or an experienced construction tradesperson, RISE may be the place for you.

- Highly competitive wage and benefits package with full healthcare coverage
- \$1,500 signing bonus
- Climate-controlled manufacturing environment
- Safer, healthier work environment
- Ergonomic workstations

Revolutionizing construction with commercial volumetric modular and YOU!

#WeAreHiring #ConstructionJobs #ManufacturingJobs #Carpenter #Electrician #Plumber #Journeyman #FortLiftOperator #HVAC #Painter #Framer #Jobs #TogetherWeRISE



#### Offsite Construction

#### **Benefits of Offsite Construction:**

- Safer working conditions fewer ladders, less silica exposure, less tools used overhead, exposure to weather, etc.
- More productive
- Adds certainty to the schedule
- Reduction of Waste
- Improved Quality
- Controlled training environment
- Etc.



## Working with IBEW

 Yellow Tagging/Labels are critical to their ability to prefab – How do we bring the IBEW and electrical contractors opposed to portability along with us? We are playing with a significant disadvantage.











#### Managing Complex Change





- Offsite
- Kitting
- Prefab
- Panelized
- Modular
- Volumetric





### Offsite Construction (Off-Site)

Most companies get started with some very basic concepts. That transfer the same job-site processes into a warehouse type environment.

- Prep
  - Unboxing, Minor Assembly, Testing
- Multi Wire Reel
  - Combine multiple wires to a single reel to the pull length
- Bends
  - Conduit bending

- Packaging
  - Grouping materials and tools together based on what and when they will be needed on site
- Logistics
  - Wearhouse staging, shipping and job staging



# Prefabrication (Pre-Fab)

Traditional on-site methods of assemblies that have been moved into a warehouse or manufacturing facility.

- Assemblies
  - Conduit
  - Cable Tray
  - MC Whips
  - Panels
  - Equipment
  - Boxes
  - Hangers


 These assemblies typically have multiple materials and manufactured items that are put together in the shop and delivered to the jobsite as components



## Construction Manufacturing (Con-Mfg)

Transformation of on-site methods of assembly into manufacturing processes of standardized assemblies to produce higher volumes that can be introduced during design, preconstruction and or sold to 3rd parties.

Standardized assemblies or DFMA are often the same assemblies but with limited configuration options.





### Where is Construction Going - DFMA

Is the combination of two methodologies; Design for Manufacture, which means the design for ease of manufacture of the parts that will form a product, and Design for Assembly, which means the design of the product for ease of assembly.



# It all starts with the People





- You have to get buy-in from the field. They need to be apart of the solution.
- Get the right people in the right place. From the field side get the person who is thinking outside of the box who is solving problems in untraditional ways. these are great guys to start the foundation in the shop for prefab because they're going to encounter different situations for different projects, and they'll find out-of-the-box solutions.
- Weekly Foreperson Prefab Meetings (15 minutes) to build comradery and open line of communication
- Getting Foreperson aligned early with their design



- Look at jobs with prefab in mind Which jobs are going to be best for prefab implementation and to what level. Some jobs you will be able to prefab a lot more than others, set a criteria for levels of offsite construction. 1 (minimal) 5 (Majority of job prefab).
- Select a good project, find a project that has a good GC that you trust and that understands the impact that the prefab will bring.
- Start small, start with receptacle boxes and MC for inwall, or lighting whips. Develop and fine tune your process on the easier prefab opportunities, as your process improves increase the amount of prefab that you're doing.
- Do not be afraid to fail some of the biggest improvements come from some of the largest failures. consider failing as part of the learning process, a failure is only a failure if you don't learn from it.




# Process Mapping




#### Shop Procurement Flow Diagram Determine Pre-fab opportunities Determine prefab Coordinate Schedule schedule SPM SCH. SI PM SPM S SCH opportunities and then fill out the Create pre-fab log/ with job schedule Is it possible? Detailing process begins Deliver spool Create spool drawings drawings to SPM LD, BIM MGR, DS, Techs Refer the detailing flowchart DS DS, SPM SPM reviews spool Obtain correct quotes on the Generate Material list Review material generated material list Create material list specific SPM to a shop ticket group SPM reviews quotes and looks for backorder, substitutions, lead times Deliver shop packet to shop SPM Write FPO/LPO Create Shop ticket Shop packet includes Select the vendor update prefab · shop ticket LD, SPM based on quotes log/Schedule Deliver PO to vendor · spool drawings create shop ticket material needs to be SPM. PM SPM · spool map (if available) tagged and held at the per group labels (if required) vendor's warehouse · Electric Files (tiger stop. plasma table) Coordinate with Superintendent 1. Shop ticket group priority 2. Delivery time and method. Pre-fab delivered to the lob site Package pre-fab for Shop Fabrication material from vendor as QA/QC on the pre-fab delivery per shop group priority. prior to shipping attach copy of the spools and installation drawing with the delivery. Rework Form QA/QC on the preif the pre-fab received Key is incorrect, rework incident is reported. Process Personal responsible Discuss feedback Installation PM: Project Manager LD: Lead Detailer Information Proce SPM: Shop Manager SI: Shon Superintendent General Process Discuss takeaways Pref-fab is installed at S: Superintendent Schedule Process the job site SCH: Scheduler detailing DS: Detailer Support

### **Process Mapping**

















#### BOX AND WHIP ASSEMBLY STATION



-SHRINK WRAP -TOTES AND LIDS



# CONDUIT RACK BUILDING STATION

OUT WORKTABLE WORKTABLE

\*\*\*\*

CONDUIT/RACK
ASSEMBLY

#### **CONDUIT RACK STATION**

DESCRIPTION-ASSEMBLE CONDUIT AND STRUT INTO CONDUIT RACKS OR BRANCH CIRCUIT ASSEMBLIES.

#### TOOLS NEEDED AT STATION


- -TAPE MEASURE
- -PENCIL
- -SHARPIE
- -PVC HEATER
- -SOCKET SET
- -IMPACT DRIVER W/ BATTERIES AND CHARGER
- -ASSORTED IMPACT BITS
- -FLATHEAD & PHILLIPS SCREWDRIVERS
- -NUTDRIVERS
- -C CLAMPS
- -NEEDLE NOSE PLIERS
- -LINEMANS PLIERS
- -WIRE STRIPPERS
- -WIRE NUT DRIVER

#### MATERIAL NEEDED AT STATION

- -SHRINK WRAP
- -TEK SCREWS
- -3/8" NUTS AND WASHERS
- -1/4" NUTS AND WASHERS
- -COBRA CLAMPS
- -8-12P STRAPS



# BOX BUILDING STATION



#### **BOX BUILDING ASSEMBLY STATION**

DESCRIPTION-PREASSEMBLE WALL BOXES WITH BRACKET, MUDRING, AND GROUND PIGTAIL.

#### TOOLS NEEDED AT STATION

- -(2) 9V IMPACT DRIVERS W/ BATTERIES AND CHARGERS
- -ASSORTED IMPACT BITS
- -FLATHEAD & PHILLIPS SCREWDRIVERS
- -WIRE NUT DRIVER
- -CHANNEL LOCK PLIERS
- -TRASH CAN
- -LOCKNUT SOCKET
- -LINEMAN PLIERS

#### MATERIAL NEEDED AT STATION

- -BOXES
- -MUDRINGS
- -BRACKETS (REG,3 BOX, & EXPANDING)
- -GROUND PIGTAILS
- -1/2" &3/4" CONNECTORS




### **Part Identification**







### Workstations












#### **Shadow Boards**









Brand: Mophorn

\$729<sup>99</sup>

Pay \$40.56/month for 18 months, interest-free upon approval for the Amazon Rewards Visa Card

Brand Mophorn


Material Stainless Steel

**Color** 4.5 square stripping machine

Handle Material Polyvinyl Chloride


#### About this item

- Cutting the line core cross section: 0.1-4.5mm2; Cutting Length: 1 9999 mm
- Stripping speed (/ h): L = 100mm, 3000-8000pcs / h (high yield)
- · Appropriate stripping wire: PVC / Teflon / silicone cable / wire glass fiber
- Exquisite outlines, simple operation and maintenance, stable performance, fast speed, and high accuracy





## Workstations (Cont.)





## Storage & Handling (Cont.)






## Storage & Handling









## Storage and Handling (Cont.)








## Storage & Handling (Cont.)








## Storage & Handling (Cont.)








#### **Standardization - Productization**





PARTIAL 46TH FLOOR - ELECTRICAL POWER PLAN

## **Interesting Ideas**










## **Buy vs Build**

Strut Hanger Pro - <a href="https://www.struthangerpro.com/">https://www.struthangerpro.com/</a>






# Technology



# Viewing the Plans & Model in the Field






## BIM/VDC



THE DIFFERENCE IS REAL







#### **Augmented Reality**





#### **Robotic Total Stations**



**Trimble** 



Leica



Sokkia



Topcon



#### 2<sup>nd</sup> Generation Robotic Total Station – Rapid Positioning Systems



- Range of 50m
- Autostationing™
- 300° of tilt for easy overhead measurements.
- Green laser: lets you measure without a prism on a wide range of surfaces.
- Retails around \$19,000





#### 360 Cameras



**Insta360 ONE X = \$400** 





**Garmin Virb 360 = \$799** 



**LG** 360 = \$99





## **Jobsite Photos**

Sequences & Actions

1 1

**1 0 0** 







**STRUCTION**SITE







## **Reality Capture**




### Reality Capture

#### What Verity Does




- 3 Hours to Process
- 8 Hours to QA and Create PDF Report
- ~50% of Steel was installed out of tolerance, 8% required follow up
- Initial results found some Steel Members 3" out of Place

Interrogate each element in Verity



View the entire project in Navisworks





## Education



#### Prefab Research – ELECTRI.org






- Labor savings of up to 50% on in-wall, rough-in installation costs.
- Material savings of up to 40%.
- Reduced material handling and inventory costs by building (or ordering) based on the quantities needed for the job and the ability to supply the labeled assemblies in exact quantities.
- Reduced on-site packaging and waste by identifying specific locations on the job to deliver prefabricated materials, thus allowing utilization of palletized assemblies.



### Industrialization Report







#### Industrialization Index Self-Evaluation

ELECTRI International asked MCA, Inc. to study and identify how Industrialization of Construction® will continue to unfold and provide ELECTRI and its members a means of getting and staying ahead. The Industrialization Index Self-Evaluation looks at each step of Industrialization and ask questions to identify where an organization falls in terms of Industrialization.

*	D		$^{\circ}$	1111	m	Δ.	~
	п	c	ч	u	ш	C	u

First and Last Name \*

Your answer

Email Address \*

Your answer

Company Name \*

Your answer







#### QR Codes to Streamline Data to the Field












#### Links to Resources

Bluebeam training.mp4

**Creating QR Codes.mp4** 











Research and Education for the Electrical Construction Industry

Josh Bone ELECTRI Executive Director josh.bone@electri.org